

CARGA DE TRANSFORMADORES

Código Ident. Nombre o N°	Estación Transformadora	Trafo N°	2015			2016			2017			2018			2019		
			Sn (1)	Carga (2)		Sn (1)	Carga (2)		Sn (1)	Carga (2)		Sn (1)	Carga (2)		Sn (1)	Carga (2)	
			MVA	MVA	%	MVA	MVA	%	MVA	MVA	%	MVA	MVA	%	MVA	MVA	%
SR1TP01	SANTA ROSA	1	30	21,47	72%	30	22,33	74%	30	23,23	77%	30	24,15	81%	30	25,12	84%
SR1TP02	SANTA ROSA	2	30	21,47	72%	30	22,33	74%	30	23,23	77%	30	24,15	81%	30	25,12	84%
SR1TP03	SANTA ROSA	3	30	21,47	72%	30	22,33	74%	30	23,23	77%	30	24,15	81%	30	25,12	84%
SU1TP01	SANTA ROSA SUR	1	30	13,45	45%	30	13,99	47%	30	14,55	48%	30	15,13	50%	30	15,73	52%
SU1TP02	SANTA ROSA SUR	2	30	13,45	45%	30	13,99	47%	30	14,55	48%	30	15,13	50%	30	15,73	52%
GP1TP01	GENERAL PICO	1	30	25,22	84%	30	26,22	87%	30	27,27	91%	30	28,36	95%	30	29,50	98%
GP1TP02	GENERAL PICO	2	30	25,22	84%	30	26,22	87%	30	27,27	91%	30	28,36	95%	30	29,50	98%
GU1TP01	GUATRACHÉ	1	10	6,90	69%	10	7,17	72%	10	7,46	75%	10	7,76	78%	10	8,07	81%
GU1TP02	GUATRACHÉ	2	10	6,90	69%	10	7,17	72%	10	7,46	75%	10	7,76	78%	10	8,07	81%
RL1TP01	REALICÓ	1	15	9,69	65%	15	10,07	67%	15	10,48	70%	15	10,89	73%	15	11,33	76%
RL1TP02	REALICÓ	2	15	9,69	65%	15	10,07	67%	15	10,48	70%	15	10,89	73%	15	11,33	76%
GA1TP01	GENERAL ACHA	1	10	9,23	92%	10	9,60	96%	10	9,98	100%	10	10,38	104%	10	10,80	108%
GA1TP02	GENERAL ACHA (futuro)	2	10			10		0%	10		0%	10		0%	10		0%
PM1TP01	PICHI MAHUIDA	1	15	1,90	13%	15	1,90	13%	15	1,90	13%	15	1,90	13%	15	1,90	13%
PM1TP02	PICHI MAHUIDA	2	15		0,00	15		0%	15		0%	15		0%	15		0%
MM1TP01	MAURICIO MAYER	1	30	17,84	59%	30	18,55	62%	30	19,30	64%	30	20,07	67%	30	20,87	70%
MA2TP01	MACACHÍN 33/33 kV	1	10	8,93	89%	10	9,29	93%	10	9,66	97%	10	10,05	100%	10	10,45	104%

(1) Potencia nominal del arrollamiento mas comprometido

(2) % respecto de Sn. Resaltar en Negritas cuando se supera el 100%

